

**SURVEY & REMONUMENTATION**

**\$7.00**  
**\$2.00**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION. LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
99 MAR -5 AM 8:28  
REG. OF DEEDS  
*Lucy Storch*

For corners in

KENT COUNTY (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>12W</u>	<u>C-9</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

**10440**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

C-9	1837	GLO	Whitcomb	Set Post
			Kent Co. Wits	1" Iron in Mon. Box
	1983	LCRC #3451	Jonker	1/2" Iron in Mon. Box
	1983	LCRC #3631	Kolehouse	Set Kent County Monument in Mon. Box
	1991	LCRC #6140	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Henry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11-26-83 and was recorded per LCRC #3631.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-9	Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #3451.
LCRC #3631	Nail & Remon. tag P. Pole N65°E 78.88'
	Chiseled "X" on conc. culv. S70°E 67.26'
	PK Nail in curb joint N60°W 41.50'
	PK Nail in curb joint S60°W 39.98'
	At C/L "X" 12 Mile Rd. and Fruitridge Ave.
	The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-9	Standard Kent County Monument in Mon. Box
	Nail & KC Remon. tag SE side new P. Pole N65°E 65.13'
	"X" cut on top S. end conc. culvert S70°E 67.29'
	PK Nail in curb joint N60°W 41.53'
	PK Nail in curb joint S60°W 39.98'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98