

MAR 08 1999

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

Lucy Standa

38 OCT -7 AM 10:15

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey

T9N R12W

C-10

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

10702

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on July 13, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-10	1837	GLO	Whitcomb	Set Post
	1940	Kent Co. Wits		Conc. Mon.
	1981	LCRC #2483	Glaza	Iron in Mon. Box
	1982	LCRC #2949	Merdzinski	Set Kent County Monument in Mon. Box
	1991	LCRC #6141	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 6-28-82 and was recorded per LCRC #2949.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 10" long iron he found inside a Mon. Box over a Conc. Mon.. Both check with Kent Co. Wits. and LCRC #2483. LCRC #2949 LCRC #6141

Nail & Remon. tag 14" Elm	S88°W	37.82'	Nail & Remon. tag 22" Elm	S88°W	38.12'
NE corner frame bldg.	S50°W	127.75'	Nail & Remon. tag 10" Apple	S45°E	74.64'
C/L 6" Apple	S45°E	74.80'	Nail & Remon. tag 8" Apple	N40°E	69.50'
C/L 6" Apple	N40°E	69.30'	S. end 12" steel culvert	N45°E	38.70'
S. end 12" steel culv.	N45°E	38.70'	Nail & Remon. 10" Pine	S45°W	77.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 Standard Kent County Monument

Nail & KC Remon. tag N. side 24" Elm	S88°W	38.12'
Nail & KC Remon. tag NE side 12" Apple	S45°E	74.64'
Nail & KC Remon. tag NW side 10" Apple	N40°E	69.53'
Nail & KC Remon. tag NE side 4" Apple	N25°W	105.32'

C/L N-S pavement is West 1.5' ±



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/24/98