

7/2 SURVEY & REMONUMENTATION
 MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 KENT COUNTY
 (County)

Located In:	Corner Code #
1. Public Land Survey	T 9N R 12W C-11
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S ___ T ___ R ___
	S ___ T ___ R ___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 OCT -7 AM 10:15
 REG. OF DEEDS
Luci Stand

10703

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on July 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-11 1837 GLO	Whitcomb	Set Post
1940 Kent Co. Wits		Conc. Mon.
1981 LCRC #2483	Glaza	Iron in Mon. Box
1982 LCRC #2948	Merdzinski	Set Kent County Monument in Mon. Box
1991 LCRC #6142	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/24/98
 CHAIRMAN Darryl Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 6-28-82 and was recorded per LCRC #2948.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Iron and remains of a Conc. Mon. he found inside a Mon. Box. Both check with Kent Co. Wit. and LCRC #2483.		
LCRC #2948	LCRC #6142	
Nail & Remon. tag 8" Apple S40°W 43.10'	Nail & Remon. tag 8" Apple	S40°W 43.04'
Nail & Remon. tag 6" Cherry N45°E 39.38'	Nail & Remon. tag 6" Cherry	N45°E 39.38'
Nail & Remon. tag 8" Cherry N35°W 87.80'	Nail & Remon. tag 8" Cherry	N35°W 87.80'
C/L Fruit Ridge Ave. joint is 3' West	Nail & Remon. tag top of guard rail post	N10°E 171.45'
On fence line to East		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument		
Nail & KC Remon. tag NW side 8" Cherry	N45°E	39.38'
Nail & KC Remon. tag NE side 10" Cherry	N35°W	87.80'
Nail & KC Remon. tag top of guard rail post	N10°E	171.45' (slope)
Nail & KC Remon. tag SE side Tri. 10" Elm	S45°W	55.50'
C/L Fruit Ridge Ave. pavement is West 3' ±		



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 9/24/98