

SURVEY'S
REMONUMENTATION

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SEP 18 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	12W	C-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 PM 12:00
REG. OF DEEDS
8517

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Kirk Breitels, in a field survey on March 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-13 1837 GLO Brookfield Set Post
- 1951 Williams & Works Conc. Mon.
- 1966-71 Kent Co. Rd. Com. Mon. Box
- 1973 Kent co. Wit. Mon. Box
- 1984 LCRC #4075 Kolehouse Set Kent County Monument
- 1991 LCRC #6144 By1 Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/17/84 and was recorded per LCRC #4075

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Iron inside a mon. box he found. Said Iron checks with Kent Co. Wit. & Rd. Com. and Williams & Works information

LCRC #4075 & #6144

Nail & KC Remon. tag NE side P. Pole	N45°W	59.61'
Nail & KC Remon. tag E. side 18" Walnut	N25°W	74.57'
Nail & KC Remon. tag SW side P. Pole	S45°E	56.18'
SW cor. Glazed tile bldg.	N30°E	68.63'
C/L manhole	S90°W	38.53'
NW cor. bldg. foundation	S30°W	103.71'
Kent Co. Mon. (C-1, T8N, R12W)	East	305.30'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN *Harry Hedges*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13 Standard Kent County Monument
- Nail & KC Remon. tag NE side P. Pole N45°W 59.61'
- Nail & KC Remon. tag E. side 20" Walnut N25°W 74.57'
- Nail & KC Remon. tag SW side P. Pole S45°E 56.18'
- SW cor. Glazed tile bldg. N30°E 68.63'
- C/L manhole S90°W 38.53'
- NW cor. bldg. foundation S30°W 103.71'
- Kent Co. Mon. (C-1, T8N, R12W) East 305.30'



Signed by Kirk Breitels

Date 6/22/95

Surveyor's Michigan License No. 30077