

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 OCT -7 AM 10:15
REG. OF DEEDS
David Stand

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 12W D-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

10704

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1			●									
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- D-1 1837 GLO Brookfield Not Set
- 1981 LCRC #2046 Glaza Set Iron on line between NE & NW corners and extended N-S 1/4 line
- 1993 LCRC #6885 Bueche Set Kent County Monument - no witnesses within 500'

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/24/98
CHAIRMAN John C. Bueche

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-1 Found BROKEN Kent County Monument (Harrison) in field, per information from above LCRC as set by John C. Bueche on the N-S 1/4 line - extending a line from the S 1/4 corner through the C 1/4 corner and measuring 2568.03' (computation per Roosien).
LCRC #6885

- Dist. From S 1/4 corner to C 1/4 corner: 2653.91'
- Dist. From C 1/4 corner to iron set on N-S 1/4 line: 2063.35' - 504.68' to N 1/4 corner
- 2653.78' E. to NE corner of Sec. 5
- 2669.24' W. to NW corner of Sec. 5

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 Established location of corner by extending a line from S 1/4 corner (Kent Co. Mon.) North through C 1/4 corner (Kent Co. Mon.) and a distance of 504.68' North of a Capped Rod (Bueche) as described in LCRC #6885. Corner fall in soybean field - decided not to set monument here but to set a witnesses monument to South and West.
Measured from S 1/4 corner to C 1/4 corner: 2653.85' Measured from C 1/4 to computed N 1/4 corner: 2568.05'
Measured E. to NE corner Sec. 5: 2653.53' Measured W. to NW corner Sec. 5: 2669.42'
Measured angle around S. side of computed corner: 180°00'45" (Roosien: 180°00'50")

See LCRC # 10705 & LCRC # 10707 for location of witness monuments.

Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/24/98

