

1/2 MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|--------------|---------------|-----|
| 1. Public Land Survey | T <u>9</u> N | R <u>12</u> W | D-2 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 OCT -7 AM 10:15
REG. OF DEEDS
Lucy Bond

10708

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on July 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|----------|----------------------------------|
| D-2 | 1837 | GLO | Whitcomb | Not Set |
| | 1943 | Kent Co. Wits | | Stone |
| | 1981 | LCRC #2046 | E. Glaza | Set RR Spike from Kent Co. Wits. |
| | 1992 | LCRC #6602 | Bueche | Set Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN *Sam Kuehn*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6602.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the RR Spike he found. Said RR Spike checks with Kent Co. Wits. & LCRC #2046.
LCRC #6602

- | | | |
|---|--------------|--------------------------|
| Nail & Remon. tag SE side P. Pole | S25°W 48.10' | On N-S 1/4 line and |
| Nail & Remon. tag NW side P. Pole | N45°E 65.02' | 0.06' S. of E-W 1/4 line |
| SW corner hse. #12800 porch (1.5' high) | S75°E 76.15' | |
| NW corner frame house | N70°E 87.42' | |
| SW corner frame house | S80°E 84.45' | |
| Glaza Iron - West | 33.04' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-2 Standard Kent County Monument
- | | |
|---|--------------|
| Nail & KC Remon. tag SE side P. Pole | S25°W 48.10' |
| Nail & KC Remon. tag NW side P. Pole | N45°E 65.02' |
| SW corner wood frame porch | S75°E 76.45' |
| NW corner frame house | N70°E 87.42' |
| SW corner frame house | S80°E 84.45' |
| Glaza Iron - West | 33.02' |
| On N-S 1/4 line and less than 0.1' S. of E-W 1/4 line | |
| On C/L N-S asph. road | |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/24/98