

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:28
REG. OF DEEDS
Luis S. ...

For corners in

KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>9N</u> R <u>12W</u>	D-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10445

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Kirk Breitels, in a field survey on Jan. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9	1837	GLO	Whitcomb	Set Post
	1935	Kent Co. Wits		Boat Spike on Stone
	1979	LCRC #1254	Merdzinski	"T" Iron
	1982	LCRC #2628	Nederveld	Set Kent County Monument
	1991	LCRC #6148	Byl	Reset Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Kuben*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 1-25-82 and was recorded per LCRC #2628.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in the same location as set in 1982 by Gordon D. Nederveld in place of the "T" Iron, Boat Spike and Stone he found. All check with Kent Co. Wits. and LCRC #1254.

LCRC #2628		LCRC #6148
Nail & Remon. tag P. Pole	N08°E 41.44'	Nail & Remon. tag 24" Maple N82°E 103.83'
Nail & Remon. tag 24" Maple	N82°E 103.83'	Nail & Remon. tag 8" Stump S02°E 50.44'
Nail & Remon. tag 8" Elm	S02°E 50.44'	Nail & Remon. tag P. Pole N10°E 42.17'
Nail & Remon. tag 30" Cherry	S75°W 61.35'	Nail & Remon. tag 12" Maple N70°E 60.58'
		Nail & Remon. tag 6" Maple S05°W 59.83'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 Standard Kent County Monument

Nail & KC Remon. tag S. side 30" Maple	N82°E 103.74'
Nail & KC Remon. tag W. side new P. Pole	N10°E 44.00'
Nail & KC Remon. tag E. side 10" Maple	S05°W 59.83'
Nail & KC Remon. tag W. side wood post	S60°E 38.78'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98