

MAR 08 1999

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>9</u> N	R <u>12</u> W	D-12
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on July 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-12 1837	GLO	Not Set
1918	Williams & Works	Stone
	Kent Co. Wits	Stone
1998	Survey Jonker	Set Capped Rerod at Intersection of 1/4 lines - did not find Stone

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/23/98
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-12 Found Capped Rerod (Jonker).

Said Capped Rerod is 0.1' S and 0.2' E. of intersection of 1/4 lines.

The Capped Rerod (Jonker) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Set Standard Kent County Monument in place of the Capped Rerod (Jonker).

Nail & KC Remon. tag E. side 12" Cherry	S05°E	9.22'
Nail & KC Remon. tag S. side 12" Cherry	N80°W	33.82'
Nail & KC Remon. tag E. side 30" Beech	N20°W	14.38'
Nail & KC Remon. tag SE side 15" Cherry	N30°E	21.88'
Nail & KC Remon. tag NE side 24" Beech	S70°E	26.99'
Fence to South is 6' ± West		
Fence to East is 8' ± South		

Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/25/98

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 OCT -7 AM 10:15
REG. OF DEEDS
[Signature]

10711

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13		*											

