

SLAVEY A  
REMONUMENTATION  
\$7.00  
\$2.00  
SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

|                                      |   |           |   |            |             |
|--------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey                | T | <u>9N</u> | R | <u>12W</u> | <u>D-13</u> |
|                                      | T | _____     | R | _____      | _____       |
|                                      | T | _____     | R | _____      | _____       |
|                                      | T | _____     | R | _____      | _____       |
| 2. Property Controlling in Section   | S | _____     | T | _____      | _____       |
|                                      | S | _____     | T | _____      | _____       |
| 3. Miscellaneous Property in Section | S | _____     | T | _____      | _____       |
|                                      | S | _____     | T | _____      | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 PM 12:00  
REG. OF DEEDS  
*Luci Sand*  
8518  
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on March 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

|      |      |                  |            |                          |
|------|------|------------------|------------|--------------------------|
| D-13 | 1837 | GLO              | Brookfield | Set Post                 |
|      | 1899 | Williams & Works |            | Pointed Stone            |
|      | 1961 | Williams & Works |            | Iron in mon. box         |
|      | 1966 | Kent Co. Wit.    |            | Mon. Box                 |
|      | 1984 | LCRC #4076       | Kolehouse  | Set Kent County Monument |
|      | 1991 | LCRC #6150       | Byl        | Kent County Monument     |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/16/84 and was recorded per LCRC #4074

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found inside a mon. box. Said 1" Iron checks with Williams & Works information and Kent Co. Wit.  
LCRC #4074 & #6150

|   |       |         |
|---|-------|---------|
| Nail & KC Remon. tag in P. Pole         | N00°E | 89.68'  |
| Nail & KC Remon. tag in P. Pole         | S00°W | 34.41'  |
| NW cor. brick garage (attached to hse.) | S20°E | 91.07'  |
| Chiseled "X" on E. end 12" conc. culv.  | N55°E | 44.75'  |
| NE cor. brick hse. #3464                | S50°E | 117.86' |
| Kent Co. Mon. (D-1, T8N, R12W)          | East  | 265.35' |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *Harry Thiede*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Standard Kent County Monument in mon. box

|   |       |         |
|---|-------|---------|
| Nail & KC Remon. tag W. side P. Pole    | N00°E | 89.68'  |
| Nail & KC Remon. tag W. side P. Pole    | S00°W | 34.41'  |
| NW cor. brick garage (attached to hse.) | S20°E | 91.07'  |
| Chiseled "X" on E. end 12" conc. culv.  | N55°E | 44.75'  |
| NE cor. brick hse. #3464                | S50°E | 117.86' |
| Kent Co. Mon. (D-1, T8N, R12W)          | East  | 265.31' |



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 6/22/95