

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:28
REG. OF DEEDS
Lucy Spauld

For corners in
KENT COUNTY

Located In: Corner Code #

1. Public Land Survey	T 9N R 12W	E-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

10447

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3					●								
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-3	1837	GLO	Whitcomb	Set Post
	1964	Kent Co. Wits		Iron in Mon. Box
	1974	LCRC #1383	Jonker	Iron in Mon. Box
	1983	LCRC #3380	Stadt	Set Kent County Monument in Mon. Box
	1991	LCRC #6152	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Tubel*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 5-16-83 and was recorded per LCRC #3380.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Russell E. Stadt in place of the Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #1383.

LCRC #3380	Vertical cut E. end conc. culv.	S30°E	72.15'	Vertical cut E. end conc. culv.	S30°E	72.15'
	Vertical cut W. end conc. culv.	S30°W	72.65'	Vertical cut W. end conc. culv.	S30°W	72.65'
	Nail & Remon. tag P. Pole	N30°E	101.39'	Nail & Remon. tag P. Pole	N30°E	101.39'
	Nail & Remon. tag P. Pole	N65°W	160.80'	Nail & Remon. tag Guy Pole	N65°W	160.70'
	On C/L E-W road, C/L road N. is 3' W.			Nail & Remon. tag P. Pole	S25°E	104.10'
	C/L road S. is 1.5' E.					

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3	Standard Kent County Monument in Mon. Box		
	Vertical cut on E. end conc. culv.	S30°E	72.15'
	Vertical cut on W. end conc. culv.	S30°W	72.65'
	Nail & KC Remon. tag NW side P. Pole	N30°E	101.39'
	Nail & KC Remon. tag S. side Guy Pole	N65°W	160.70'
	Nail & KC Remon. tag W. side P. Pole	S25°E	104.10'
	On C/L E-W road, C/L road N. is 3' West, C/L road S. is 1.5' E.		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98