

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|---------------|-----|
| 1. Public Land Survey | T <u>9</u> N | R <u>12</u> W | E-4 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 26, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|--------------|--------------------------------------|
| E-4 | 1837 | GLO | Whitcomb | Set Post |
| | 1944 | Kent Co. Wits | | 3/4" Iron on Stone |
| | 1983 | LCRC #3621 | Chettleburgh | Set Kent County Monument in Mon. Box |
| | 1991 | LCRC #6153 | Byl | Kent County Monument in Mon. Box |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas M. Chettleburgh on 11-25-83 and was recorded per LCRC #3621.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh in place of the 5/8" Iron Pipe he found inside a Mon. Box. Iron Pipe checks with Kent Co. Wits. and information of others.

- | | | | | | |
|------------|-----------------------------|------------|------------|-----------------------------|---------------|
| LCRC #3621 | Nail & Remon. tag 36" Maple | E 174.39' | LCRC #6153 | Nail & Remon. tag 36" Maple | N90°E 174.39' |
| | Nail & Remon. tag 10" Apple | SE 57.42' | | Nail & Remon. tag 12" Apple | S55°E 57.42' |
| | Nail & Remon. tag 12" Apple | SSE 75.35' | | Nail & Remon. tag 12" Apple | S40°E 75.40' |
| | Nail & Remon. tag 9" Apple | SSW 71.28' | | Nail & Remon. tag 10" Apple | S55°W 71.31' |
| | Nail & Remon. tag 6" Apple | SW 58.33' | | Nail & Remon. tag 10" Apple | S70°W 58.37' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-4 Standard Kent County Monument in Mon. Box
- | | | |
|---|-------|---------|
| Nail & KC Remon. tag N. side 40" Maple | N90°E | 174.41' |
| Nail & KC Remon. tag E. side 12" Apple | S55°W | 71.34' |
| Nail & KC Remon. tag S. side 12" Apple | S70°W | 58.40' |
| Nail & KC Remon. tag W. side 14" Walnut | N05°E | 241.12' |
| Nail & KC Remon. tag | | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:29
REG. OF DEEDS
David S. ...

10448

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN *Harold Fisher*

Signed by *Kirk Breitels*

Date 2/19/98

Surveyor's Michigan License No. 30077

