

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:29  
REG. OF DEEDS  
*Lucy Stand*

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N R 12W	E-5
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

10449

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5				●								
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Jan. 22, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5	1837	GLO	Whitcomb	Set Post
	1935	Kent Co. Wits		3/4" Iron
	1983	LCRC #3622	Chettleburgh	Set Kent County Monument in Mon. Box
	1991	LCRC #6154	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas M. Chettleburgh on 11-25-83 and was recorded per LCRC #3622.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh in place of the 1/2" Iron Pipe inside a 3/4" Iron Pipe he found inside a Mon. Box. Both Iron Pipes checks with Kent Co. Wits.

LCRC #3622	Nail & Remon. tag 10" Spruce	NE	53.26'	LCRC #6154	Nail & Remon. tag 12" Spruce	N40°E	53.26'
	Nail & Remon. tag P. Pole	SE	74.12'		Nail & Remon. tag P. Pole	S40°E	74.17'
	Nail & Remon. tag 25" Maple	SSW	73.53'		Nail & Remon. tag 28" Maple	S45°W	55.46'
	Nail & Remon. tag 28" Maple	SW	56.01'		SW corner house foundation	N50°W	98.07'
	SW corner House	NW	98.00'		SE corner brick porch pillar	N30°W	67.65'
	SE corner porch pillar	NNW	67.60'				

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 Standard Kent County Monument in Mon. Box	Nail & KC Remon. tag NW side 12" Spruce	N40°E	53.26'
	Nail & KC Remon. tag NE side P. Pole	S40°E	74.17'
	Nail & KC Remon. tag NW side 30" Maple	S45°W	55.46'
	SW corner house foundation	N50°W	98.07'
	SE corner brick porch pillar	N30°W	67.65'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98