

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N	R <u>12</u> W	<u>E-7</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

Luis Standa

98 MAR -5 AM 8:29

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10451

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitel, in a field survey on Jan. 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-7	1837	GLO	Whitcomb	Set Post
	1974	Kent Co. Wits		Mon. Box
	1979	LCRC #1311	Nederveld	Iron in Mon. Box
	1983	LCRC #3655	Nederveld	Set Kent County Monument in Mon. Box
	1991	LCRC #6156	Byl	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Tubel*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 12-16-83 and was recorded per LCRC #3655.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #1311.

LCRC #3655		LCRC #6156
SE corner house foundation	NNW 129.70'	SE corner house foundation N25°W 129.75'
Nail & Remon. tag P. Pole	NE 71.30'	Nail & Remon. tag P. Pole N45°E 71.36'
Nail & Remon. tag P. Pole	SE 71.20'	Nail & Remon. tag P. Pole S45°E 71.26'
NW corner conc. culvert	SW 75.20'	Nail & Remon. tag 16" Apple S25°W 100.62'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Standard Kent County Monument in Mon. Box	
SE corner house foundation	N25°W 129.75'
Nail & KC Remon. tag NW side P. Pole	N45°E 71.36'
Nail & KC Remon. tag NE side P. Pole	S45°E 71.34'
Chiseled "X" on top W. end concrete culvert	S30°W 75.78'



Signed by *Kirk Breitel*
Surveyor's Michigan License No. 30077

Date 2/19/98