

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 JUL 14 AM 9:54

Leif J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located in:	Corner Code #
1. Public Land Survey	T ^{9N} R ^{12W}	F-1
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

10656

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1	1837	GLO	Whitcomb	Not Set
	1968	Kent Co. Wits		1/2" Iron
	1980	LCRC #1384	Jonker	Set RR Spike on Twp. line
	1992	LCRC #6604	Bueche	Set Kent County Monument
	1994	LCRC #7533	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/25/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6604.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1	Found BROKEN Kent Co. MoN. (Harrison) per wit. from above LCRC as set by John C. Bueche in place of the RR Spike he found. RR Spike checks with LCRC #1384. Removed and reset Kent Co. Mon. LCRC #6604	LCRC #7533
Nail & Remon. tag P. Pole	N35°E 39.45'	Nail & Remon. tag P. Pole N35°E 39.44'
Nail & Remon. tag P. Pole	West 69.33'	Nail & Remon. tag P. Pole West 69.33'
Nail & Remon. tag 8" Locust	N80°E 20.04'	Nail & Remon. tag 8" Locust N80°E 20.04'
Nail & Remon. tag wood fc. post	South 108.3'	Nail & Remon. tag wood fence post S00°E 117.37'
Mon. Box West 16.85'		Kent Co. Mon. (F-13, T10N, R12W) N90°W 16.86'
C/L bit. West 7.5'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1	Standard Kent County Monument
Nail & KC Remon. tag W. side P. Pole	N35°E 39.42'
Nail & KC Remon. tag S. side P. Pole	West 69.27'
Nail & KC Remon. tag N. side Tw. 6" Locust	N80°E 20.04'
Nail & KC Remon. tag W. side 6" x 6" wood corner fc. post	S00°E 117.37'
Kent Co. Mon. (F-13, T10N, R12W)	N90°W 16.88'
C/L asph. road is West 7.5' ±	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 6/25/98