

\$7.00  
\$2.00

MAR 08 1999

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey
 

T	<u>9</u> N	R	<u>12</u> W	
T		R		<u>F-6</u>
T		R		
T		R		
- 2. Property Controlling in Section
 

S		T		R	
S		T		R	
- 3. Miscellaneous Property in Sec.
 

S		T		R	
S		T		R	

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 NOV 16 AM 8:00  
 REG. OF DEEDS  
*Lucy Bond*

10929

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-6 1837	GLO	Not Set
	Williams & Works	No information
	Kent Co. Wits	No information

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 9/24/98  
 CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-6 Established Intersection of 1/4 lines - falls on remains of an E-W fence ±. No N-S occupation nearby.

Minimal information in this section for measurement comparisons.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-6 Set Standard Kent County Monument at the Intersection of 1/4 lines.
 

Nail & KC Remon. tag W. side 10" Elm	S45°W	16.95'
Nail & KC Remon. tag S. side 10" Cherry	N85°W	12.40'
Nail & KC Remon. tag NW side P. Pole	N35°E	96.24'
Nail & KC Remon. tag E. side 48" Oak	S25°E	543.50'
- On remains of E-W fence



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 11/12/98