

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>12</u> W	F-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:29
REG. OF DEEDS
Barry Stuber

10456
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- F-11 1837 GLO Whitcomb Set Post
- 1906 Williams & Works Stone
- 1935 Williams & Works 1/2" Iron
- 1935 Kent Co. Wits. 1/2" Iron
- 1984 LCRC #3941 Kolehhouse Set Kent County Monument
- 1991 LCRC #6167 Byl Reset Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Stuber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehhouse on 10-3-84 and was recorded per LCRC #3941.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

F-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl at the same location as set in 1984 by Randy J. Kolehhouse in place of the Capped Rod over a 1" Iron surrounded by Stones with an old wood stake. All check with Williams & Works information and Kent Co. Wits.

LCRC #3941	Nail & Remon. tag P. Pole S70°W 115.10'	Nail & Remon. tag P. Pole S70°W 115.02'
	NW leg CP tower S25°E 104.15'	NW corner CP tower S25°E 103.49'
	SE corner of house N45°W 88.05'	SE corner house N45°W 88.13'
	C/L (W. side) 10" Apple N40°E 46.80'	Nail & Remon. tag 10" Apple N40°E 46.99'
	In C/L 11 Mile Rd. E-W	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- F-11 Standard Kent County Monument
- Nail & KC Remon. tag S. side P. Pole S70°W 115.02'
- NW corner CP tower at grade S25°E 103.49'
- SE corner of house N45°W 88.13'
- Nail & KC Remon. tag N. side P. Pole S80°E 179.56'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98