

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAY 21 AM 8:32  
REG. OF DEEDS  
*Lucy Standa*

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 9N R 12W      G-8
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

10624

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on March 2, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1837 GLO Whitcomb Set Post  
Kent Co. Wits No desc. - witnesses given  
1990 LCRC #5600 Bueche Set Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 4/30/98  
CHAIRMAN Harry Bueche

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 7-16-90 and was recorded per LCRC#5600.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Beuche in place of the 1" Round Iron he found. Said Round Iron checks measurements of others. Kent Co. Wits. are to a different corner.  
LCRC #5600

- Nail & Remon. tag E. side 8" Elm      N40°E    2.72'
- Nail & Remon. tag S. side 28" Beech    S75°E    25.86'
- Nail & Remon. tag W. side 24" Maple    S20°E    63.63'
- Nail & Remon. tag W. side 18" Maple    S40°W    39.16'
- Nail & Remon. tag S. side 16" Maple    N80°W    17.99'
- Fence E-W is North 14' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Standard Kent County Monument  
Nail & KC Remon. tag E. side 10" Elm    N40°E    2.72'  
Nail & KC Remon. tag S. side 30" Beech    S75°E    25.89'  
Nail & KC Remon. tag W. side 26" Maple    S20°E    63.66'  
Nail & KC Remon. tag W. side 22" Maple    S40°W    39.21'  
Nail & KC Remon. tag S. side 18" Maple    N80°W    17.99'  
E-W fence is North 14' ±



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 4/30/98