

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>12W</u> | <u>G-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|-----------------|----------|--|
| G-12 1837 GLO | Whitcomb | Set Post |
| Survey | Roosien | Set Iron at Rock found by old fence post |
| 1990 LCRC #5601 | Bucche | Set Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6-1-90 and was recorded per LCRC#5601.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Capped Rod he found. Said Capped Rod checks with Roosien survey information.
LCRC #5601

- | | |
|--|--------------|
| Nail & Remon. tag E. side 36" Beech | N10°W 30.00' |
| Nail & Remon. tag N. side 8" dead tree | N80°W 4.50' |
| Nail & Remon. tag NW side 8" Elm | N50°E 18.49' |
| Nail & Remon. tag E. side 14" Beech | S15°E 28.26' |
| Nail & Remon. tag S. side 24" Oak | S50°E 59.96' |

At fence corner for fences N-S & E

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Standard Kent County Monument

- | | |
|--|--------------|
| Nail & KC Remon. tag E. side 40" Beech | N10°W 29.95' |
| Nail & KC Remon. tag NW side dead 8" Elm | N50°E 18.45' |
| Nail & KC Remon. tag E. side 18" Beech | S15°E 28.30' |
| Nail & KC Remon. tag S. side 27" Oak | S50°E 59.96' |
| Nail & KC Remon. tag N. side 8" Cherry | S90°W 22.87' |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAY 21 AM 8:32
REG. OF DEEDS
Luc St. Paul

10626

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/30/98

CHAIRMAN *John C. Bueche*

Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 4/30/98

