

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

SECTION

STATE OF MICHIGAN
COUNTY OF ALLEN
RECEIVED FOR RECORD
98 MAY 21 AM 8:33
REG. OF DEEDS
Lucy Bond

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>9N</u> R <u>12W</u> | <u>H-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

10627

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-1 1837 GLO Whitcomb Not Set
1992 LCRC #6606 Bueche Set Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/30/98
CHAIRMAN *Harry Huer*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC#6606.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche on the Township line 36.30' East of the South 1/4 corner of Sec. 34, T10N, R12W.

- LCRC #6606
- | | | | |
|---|-------|--------|----------------------------|
| Nail & Remon. tag S. side 8" Ash | S80°E | 29.03' | Fence West is South 2' ± |
| Nail & Remon. tag W. side 8" Ash | N40°E | 17.67' | Fence South os West 1.5' ± |
| Nail & Remon. tag SE side 30" Beech | S50°W | 31.80' | |
| Nail & Remon. tag W. side 8" Poplar | S30°E | 12.11' | |
| Nail & Remon. tag S. side 6" Oak | N40°W | 14.81' | |
| Kent Co. Mon. (S 1/4 cor. Sec 34, 10-12) East | | 36.30' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-1 Standard Kent County Monument
- | | | |
|--|-------|--------|
| Nail & KC Remon. tag S. side 4" Ash | S80°E | 29.02' |
| Nail & KC Remon. tag W. side 10" Ash | N40°E | 17.67' |
| Nail & KC Remon. tag SE side 32" Beech | S50°W | 31.78' |
| Nail & KC Remon. tag W. side 8" Cherry | S30°E | 12.11' |
| Nail & KC Remon. tag S. side 4" Oak | N40°W | 14.81' |
| Nail & KC Remon. tag S. side 10" Ash | N80°E | 24.84' |
| Kent Co. Mon. (H-13, T10N, R12W) West | | 36.30' |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 4/30/98