

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>12W</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 8:29

REG. OF DEEDS
Lucy St. Paul

10467

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-11 1837 GLO	Whitcomb	Set Post
1967 Kent Co. Wits		Concrete Monument
1976 LCRC #911	Bonnema	Concrete Monument
1982 LCRC #2944	Merdzinski	Set Kent County Monument
1995 LCRC #8296	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 4-12-82 and was recorded per LCRC #2944.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Concrete Monument he found. Said Concrete Monument checks with Kent Co. Wits. and LCRC #911.

LCRC #2944	LCRC #8296		
Nail & Remon. tag P. Pole	N25°E 48.60'	Nail & Remon. tag P. Pole	N25°E 48.60'
Nail & Remon. tag 16" Cherry	S65°E 100.93'	Nail & Remon. tag 30" Cherry	S65°E 100.95'
Nail & Remon. tag cor. fc. post	S40°E 51.68'	Nail & Remon. tag cor. fc. post	S40°E 51.86'
NW corner garage foundation	S35°W 168.56'	NW corner garage foundation	S35°W 168.56'
NW corner MBT Box	S65°W 84.10'	NW corner MBT Box	S65°W 84.10'

On C/L "X" intersection
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 Standard Kent County Monument	
Nail & KC Remon. tag W. side P. Pole	N25°E 48.60'
Nail & KC Remon. tag N. side 30" Cherry	S65°E 100.90'
Nail & KC Remon. tag W. side cor. fence post	S40°E 51.86'
NW corner garage foundation	S35°W 168.56'
NW corner Tele. Box	S65°W 84.10'
On C/L "X" intersection	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/19/98