

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 08 1999

\$7.00  
\$2.00

SECTION \_\_\_\_\_

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- |                                    |                          |       |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey              | T <u>9N</u> R <u>12W</u> | I-1   |
|                                    | T _____ R _____          | _____ |
|                                    | T _____ R _____          | _____ |
|                                    | T _____ R _____          | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____ |
|                                    | S _____ T _____ R _____  | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____ |
|                                    | S _____ T _____ R _____  | _____ |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:29  
REG. OF DEEDS  
*Lucy Stand*

10468

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |     |      |               |           |                          |
|-----|------|---------------|-----------|--------------------------|
| I-1 | 1837 | GLO           | Whitcomb  | Set Post                 |
|     | 1968 | Kent Co. Wits |           | Iron                     |
|     | 1979 | LCRC #1372    | VanKooten | "T" Iron in Mon. Box     |
|     | 1981 | LCRC #3201    | Nederveld | "T" Iron in Mon. Box     |
|     | 1983 | LCRC #3382    | Stadt     | Set Kent County Monument |
|     | 1991 | LCRC #5994    | Byl       | Kent County Monument     |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 5-5-83 and was recorded per LCRC #3382.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found Kent Co. Mon. (Harrison) per wits. from above LCRC as set by Russell E. Stadt on Twp. line in place of the "T" Iron inside Mon. Box he found. "T" Iron and Mon. Box check Kent Co. Wits. and LCRC's #1372 & #3201.

- |            |                             |       |         |            |                                  |       |         |
|------------|-----------------------------|-------|---------|------------|----------------------------------|-------|---------|
| LCRC #3382 | Nail & Remon. tag 10" Elm   | N55°E | 64.58'  | LCRC #5994 | Nail & Remon. tag P. Pole        | S40°W | 107.20' |
|            | Nail & Remon. tag 8" Poplar | S45°E | 73.45'  |            | Nail & Remon. tag P. Pole        | N40°W | 134.73' |
|            | Nail & Remon. tag P. Pole   | S40°W | 107.16' |            | Nail & Remon. tag 12" Poplar     | N45°E | 75.86'  |
|            | Nail & Remon. tag P. Pole   | N40°W | 134.73' |            | Nail & Remon. tag 10" Elm        | S35°E | 94.42'  |
|            | Kent Co. Mon. (I-13, 10-12) | West  | 60.58'  |            | Kent Co. Mon. (SW cor. 35-10-12) | S90°W | 60.56'  |
- C/L N-S blacktop road is West 28.7'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 Standard Kent County Monument
- |                                         |       |         |
|-----------------------------------------|-------|---------|
| Nail & KC Remon. tag E. side P. Pole    | S40°W | 107.13' |
| Nail & KC Remon. tag SW side P. Pole    | N40°W | 134.73' |
| Nail & KC Remon. tag SE side 12" Poplar | N45°E | 75.86'  |
| Nail & KC Remon. tag SW side 12" Elm    | S35°E | 94.42'  |
| Nail & KC Remon. tag SW side 14" Elm    | S55°E | 79.20'  |
| Kent Co. Mon. (I-13, T10N, R12W)        | S90°W | 60.60'  |
- C/L N-S blacktop road is West 29' ±



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98