

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION _____

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 9N R 12W

I-3

2. Property Controlling in Section

S _____

T _____

R _____

3. Miscellaneous Property in Sec.

S _____

T _____

R _____

S _____

T _____

R _____

REG. OF DEEDS

Lucy [Signature]

98 MAR -5 AM 8:29

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10470

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breittels, in a field survey on Jan. 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-3 1837 GLO Whitcomb Set Post
- 1968 Kent Co. Wits 3/4" Iron
- 1980 LCRC #1325 Nelson 3/4" Iron Rod
- 1982 LCRC #2938 Merdzinski Set Kent County Monument
- 1995 LCRC #8298 Breittels Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 4-15-82 and was recorded per LCRC #2938.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Solid Iron over ± a 2nd 3/4" Iron he found. Both Irons check with Kent Co. Wits. and LCRC #1325.

- | | |
|---|---|
| LCRC #2938 | LCRC #8298 |
| "X" cut S. end conc. culv. S85°W 103.78' | "X" cut S. end conc. culv. S85°W 103.75' |
| "X" cut N. end conc. culv. N70°W 93.75' | "X" cut N. end conc. culv. N70°W 93.75' |
| "X" cut S. end conc. culv. N20°W 103.60' | "X" cut S. end conc. culv. N20°W 103.60' |
| Nail & Remon. tag P. Pole N45°W 81.00' | Nail & Remon. tag P. Pole N45°W 81.00' |
| Nail & Remon. tag 30" Walnut S20°E 68.48' | Nail & Remon. tag 36" Walnut S20°E 68.52' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-3 Standard Kent County Monument
- "X" cut on S. end conc. culvert S85°W 103.75'
- "X" cut on N. end conc. culvert N70°W 93.75'
- "X" cut on S. end conc. culvert N20°W 103.60'
- Nail & KC Remon. tag SW side P. Pole N45°W 81.00'
- Nail & KC Remon. tag W. side 36" Walnut S20°E 68.52'
- C/L 15 Mile Rd. running West is 1.5' North
- C/L Sparta Ave. N-S is 0.5' West



Signed by Kirk Breittels
Surveyor's Michigan License No. 30077

Date 2/19/98