

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>12W</u>	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

98 MAR -5 AM 8:29

REG. OF DEEDS

[Signature]

10472

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-5	1837	GLO	Whitcomb	Set Post
	1963	Kent Co. Wits		Iron
	1978	LCRC #1195	Jonker	PK Nail
	1983	LCRC #3377	Stadt	Set Kent County Monument
	1995	LCRC #8300	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on 5-10-83 and was recorded per LCRC #3377.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Russell E. Stadt in place of the 1" Iron he found. Said Iron checks with Kent Co. Wits. and LCRC #1195.

LCRC #3377	LCRC #8300
Nail & Remon. tag 18" Walnut N30°W 85.58'	Nail & Remon. tag 26" Walnut N30°W 85.52'
Nail & Remon. tag P. Pole S88°W 52.97'	Nail & Remon. tag P. Pole S88°W 52.97'
Nail & Remon. tag MBT Pole East 34.28'	Nail & Remon. tag MBT Pole S90°E 35.78'
Nail & Remon. tag 4" Elm N45°W 53.46'	
On C/L road N-S	
Fence line to West is 1.5' North	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Standard Kent County Monument

Nail & KC Remon. tag W. side 26" Walnut	N30°W	85.52'
Nail & KC Remon. tag S. side P. Pole	S88°W	52.97'
Nail & KC Remon. tag S. side Tele. Pole	S90°E	35.73'
Nail & KC Remon. tag SE side fence post	S45°W	44.40'

On C/L N-S road (Sparta Ave.)



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/19/98