

**SURVEY & REMONUMENTATION**

~~\$7.00~~  
\$2.00

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In:	Corner Code #
T <u>9N</u> R <u>12W</u>	<u>I-6</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6	*1837	GLO	Whitcomb	Set Post
			Kent Co. Wits	Iron Pipe
	1978	LCRC #1195	Jonker	1" Square Bolt
	1982	LCRC #2630	Nederveld	Set Kent County Monument
	1995	LCRC #8301	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 1-25-82 and was recorded per LCRC #2630.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the Square Iron & 1/2" Iron he found. Both Irons check with Kent Co. Wits. and LCRC #1195.

LCRC #2630	LCRC #8301
Nail & Remon. tag Guy Pole N76°E 27.21'	Nail & Remon. tag Guy Pole N76°E 27.21'
Nail & Remon. tag P. Pole N64°W 27.14'	Nail & Remon. tag P. Pole N64°W 27.14'
Nail & Remon. tag P. Pole S18°W 116.04'	Nail & Remon. tag P. Pole S18°W 115.98'
Nail & Remon. tag T. Pole S20°E 81.96'	Nail & Remon. tag T. Pole S20°E 81.87'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Standard Kent County Monument	
Nail & KC Remon. tag S. side Guy Pole	N76°E 27.21'
Nail & KC Remon. tag N. side P. Pole	N64°W 27.10'
Nail & KC Remon. tag E. side P. Pole	S18°W 115.98'
Nail & KC Remon. tag W. side CATV Pole	S20°E 81.79'
Nail & KC Remon. tag NW side CATV Pole	N40°E 50.68'

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:29  
REG. OF DEEDS  
*Lucy Stand*

10473

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1900 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Harry Huber*



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98