

**SURVEY & REMONUMENTATION**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

SECTION \_\_\_\_\_

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- 1. Public Land Survey T 9N R 12W I-11
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

I-11	1837	GLO	Whitcomb	Set Post
	1971	Kent Co. Wits		1/2" Iron in Mon. Box
	1977	LCRC #1023	Merdzinski	3/4" Iron in Mon. Box
	1982	LCRC #2940	Merdzinski	Set Kent County Monument in Mon. Box
	1995	LCRC #8306	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 4-13-82 and was recorded per LCRC #2940.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #1023.

LCRC #2940		LCRC #8306	
Nail & Remon. tag P. Pole	East 49.77'	Nail & Remon. tag P. Pole	S90°E 49.80'
Nail & Remon. tag T. Pole	S50°W 55.59'	Nail & Remon. tag 30" Apple	N30°E 118.30'
Nail & Remon. tag T. Pole	N50°W 64.24'	Nail & Remon. tag Quad 10" Elm	S70°W 69.61'
Nail & Remon. tag 16" Apple	N30°E 118.66'	Nail & Remon. tag 6" Maple	S50°E 51.83'
Nail & Remon. tag 8" Pine	S50°E 55.66'	Nail & Remon. tag 26" Maple	N50°W 78.75'
C/L Sparta Ave. is 1' West, On C/L 11 Mile Rd.		C/L Manhole	N85°W 18.20'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-11 Standard Kent County Monument	
Nail & KC Remon. tag S. side P. Pole	S90°E 49.80'
Nail & KC Remon. tag SE side 30" Apple	N30°E 118.30'
Nail & KC Remon. tag N. side Quad 10" Elm	S70°W 69.61'
Nail & KC Remon. tag SW side 8" Maple	S50°E 51.75'
Nail & KC Remon. tag NE side 28" Maple	N50°W 78.75'
C/L Manhole	N85°W 18.20'
C/L Sparta Ave. is 1' West & on C/L 11 Mile Rd. to West	

Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 MAR -5 AM 8:30  
 REG. OF DEEDS  
*Lucy Sand*

10478

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 2/19/98  
 CHAIRMAN [Signature]

