

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

\$7.00
\$2.00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:30
REG. OF DEEDS
Luis Standa

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>12</u> W	<u>I-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10479
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 22, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | | |
|------|------|---------------|-----------|--------------------------------------|
| I-12 | 1837 | GLO | Whitcomb | Set Post |
| | 1971 | Kent Co. Wits | | Mon. Box |
| | 1972 | LCRC #3559 | VanKooten | Solid Bar in Mon. Box |
| | 1983 | LCRC #3630 | Kolehouse | Set Kent County Monument in Mon. Box |
| | 1995 | LCRC #8307 | Breitels | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Randy J. Kolehouse*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11-26-83 and was recorded per LCRC #3630.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- I-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Solid Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #3559.
- | | | | |
|-------------------------------|---------------|----------------------------------|---------------|
| LCRC #3630 | | LCRC #8307 | |
| Nail & Remon. tag P. Pole | S20°W 148.65' | Nail & Remon. tag P. Pole | S20°W 148.65' |
| Nail & Remon. tag P. Pole | 152.00' | Nail & Remon. tag P. Pole | S70°E 152.00' |
| C/L traffic sign plst | N35°W 28.6' | C/L Catch Basin | S85°W 19.05' |
| C/L C.B. | S85°W 19.05' | W'y edge pavement N. bd. M-37 | N60°E 1.10' |
| W'y edge pavement N. bd. M-37 | N60°E 4.98' | Face of E'y leg "wrong way" sign | S10°E 67.07' |
- On C/L Sparta Ave. ext. & on fence line West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-12 Standard Kent County Monument
- | | | |
|--|-------|---------|
| Nail & KC Remon. tag W. side P. Pole | S20°W | 148.65' |
| Nail & KC Remon. tag N. side P. Pole | S70°E | 151.82' |
| C/L Catch Basin | S85°W | 19.15' |
| Westerly edge pavement of N. bound M-37 | N60°E | 1.10' |
| Face of Easterly leg of "wrong way" sign | S10°E | 68.20' |
- On C/L Sparta Ave. extended.



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98