

\$7.00 ORIGINAL  
\$2.00

SEP 13 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	12W	I-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 JUN 29 PM 12:00

REG. OF DEEDS  
*Lucy Bond*

8523

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Kirk Breitels, in a field survey on Jan. 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13	1837	GLO	Brookfield	Set Post
	1967	Kent Co. Wit.		1" Iron in mon. box
	1983	LCRC #3559	VanKooten	Mon. Box
	1983	LCRC #3628	Kolehouse	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/26/83 and was recorded per LCRC #3628

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron over a 1" Iron inside a mon. box he found. Both Irons check with Kent Co. Wit. and LCRC #3559.  
LCRC #3628

NE cor. hse. fnd.	S15°W	63.25'
NW cor. hse. fnd.	S55°W	78.80'
SW cor. hse. fnd.	N30°E	40.89'
Nail & KC Remon. tag NE side P. Pole	N50°W	46.07'
1/2" Solid Iron	East	60.40'
Mon. Box 60.40' East & 1.65' North		
Monument is at C/L "X" 10 Mile Rd. & Sparta Ave. North		

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *Harry Hubert*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Standard Kent County Monument

NE cor. hse. fnd.	S15°W	63.18'
NW cor. hse. fnd.	S55°W	78.68'
SW cor. hse. fnd.	N30°E	40.89'
Nail & KC Remon. tag NE side P. Pole	N50°W	46.16'
Kent Co. Mon. (I-1, T8N, R12W)	S90°E	60.38'
Mon. Box 60.40' East & 1.65' North		
Monument is at C/L "X" 10 Mile Rd. & Sparta Ave. North		



Signed by *Kirk Breitels* Date 3/20/95  
Surveyor's Michigan License No. 30077