

**SURVEY & REMONUMENTATION**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00  
\$2.00

SECTION \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:30  
REG. OF DEEDS  
*Eric David*

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                    |                            |       |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey              | T <u>9</u> N R <u>12</u> W | J-1   |
|                                    | T _____ R _____            | _____ |
|                                    | T _____ R _____            | _____ |
|                                    | T _____ R _____            | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____ |
|                                    | S _____ T _____ R _____    | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____ |
|                                    | S _____ T _____ R _____    | _____ |

10480

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1	1837 GLO	Whitcomb	Not Set
	1971 LCRC #6	Bonnema	Boat Spike
	1992 LCRC #6608	Bueche	Set Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6608.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


J-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Boat Spike he found. Said Boat Spike checks with LCRC #6  
LCRC #6608

Nail & Remon. tag SE side 20" Maple	N10°E 39.19'
Nail & Remon. tag S. side 24" Maple	N70°W 80.60'
SW corner of house #1190	N05°E 104.75'
Nail & Remon. tag E. side TP	S00°W 30.33'
Kent Co. Mon. (S 1/4 cor. Sec. 35, 10-12)	N90°W 30.00'

C/L road is 1' South  
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Standard Kent County Monument	
Nail & KC Remon. tag SE side 24" Maple	N10°E 39.23'
Nail & KC Remon. tag S. side 24" stump	N70°W 80.64'
SW corner of house #1190 (siding)	N05°E 104.75'
Nail & KC Remon. tag E. side Tel. Pole	S00°W 30.48'
Kent Co. Mon. (J-13, T10N, R12W)	N90°W 29.99'
C/L E-W road is South 1'	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/19/98