

**SURVEY & REMONUMENTATION**

**\$7.00**  
**\$2.00**

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>9</u> N R <u>12</u> W	<u>J-10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 NOV 16 AM 8:00  
REG. OF DEEDS  
*Luigi Standa*

**10930**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on Oct. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

J-10 1837 GLO Not Set  
Williams & Works No information  
Kent Co. Wits No information

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/22/98  
CHAIRMAN [Signature]

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J-10 Established Intersection of 1/4 lines and found E-W fence to be 3' ± South and to be on a fence to North

Intersection of 1/4 lines computes to survey work by Hackbardt in the SE 1/4 of the SE 1/4 of this section.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J-10 Set Standard Kent County Monument at the Intersection of 1/4 lines.  
Nail & KC Remon. tag N. side 10" Oak N90°E 50.25'  
Nail & KC Remon. tag W. side 15" Oak N10°E 24.99'  
Nail & KC Remon. tag SW side 6" Oak N40°W 32.25'  
Nail & KC Remon. tag SE side 18" Stump S60°W 7.32'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 11/12/98