

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:	Corner Code #
T 9N R 12W	J-11
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on April 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-11	1837	GLO	Whitcomb	Set Post
		Kent Co. Wits		No desc. of corner - witnesses given
1982	LCRC #3559	VanKooten		Solid Iron
1983	LCRC #3629	Kolehouse		Set Kent County Monument
1995	LCRC #8312	Breitels		Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/30/98

CHAIRMAN Randy Kulehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11-26-83 and was recorded per LCRC #3629.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1/2" Solid Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #3559.

LCRC #3629	LCRC #8312
Nail & Remon. tag 18" Oak N35°W 18.87'	Nail & Remon. tag 30" Oak N35°W 18.85'
Nail & Remon. tag 4" Cherry N85°W 20.78'	Nail & Remon. tag 6" Cherry N85°W 20.78'
Nail & Remon. tag 8" Maple S50°W 32.25'	Nail & Remon. tag 10" Maple S50°W 32.19'
Nail & Remon. tag 10" Maple S10°W 19.57'	Nail & Remon. tag 12" Maple S10°W 19.59'
Nail & Remon. tag 6" Ash N45°E 28.20'	Nail & Remon. tag 9" Ash N45°E 28.13'
At remains of fence corner S-E-W	At remains of fence corner S-E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Standard Kent County Monument
Nail & KC Remon. tag W. side 30" Oak N35°W 18.85'
Nail & KC Remon. tag N. side 8" Cherry N85°W 20.78'
Nail & KC Remon. tag SE side 10" Maple S50°W 32.19'
Nail & KC Remon. tag W. side 12" Maple S10°W 19.59'
Nail & KC Remon. tag SE side 9" Ash N45°E 28.13'
At remains of fence corner S-E-W



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 4/30/98

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAY 21 AM 8:33
REG. OF DEEDS
W. J. [Signature]

10629

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													