

\$7.00
\$2.00
SEP 18 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
1. Public Land Survey T 9N. R 12W.	J-13
T R	
T R	
T R	
2. Property Controlling S T R	
in Section S T R	
3. Miscellaneous S T R	
Property in Sec. S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 AM 11:59
REG. OF DEEDS
8524
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on Jan. 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Spike
	1983	LCRC #3559	VanKooten	1" Iron in mon. box
	1983	LCRC #3627	Kolehouse	Set Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/26/83 and was recorded per LCRC #3627

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC #3559.

LCRC #3627

Nail & KC Remon. tag N. side 12" Maple	S75°W	126.94'
Nail & KC Remon. tag NW side P. Pole	S45°W	62.75'
NW cor. hse. fnd.	S45°E	181.50'
Iron in mon. box (N 1/4, Sec. 2, T8N, R12W)	East	46.47'

Monument is in C/L 10 Mile Rd. blacktop

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN Randy Kolehouse

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Standard Kent County Monument		
New Nail & KC Remon. tag N. side 12" Maple	S75°W	126.94'
Nail & KC Remon. tag NW side P. Pole	S45°W	62.75'
Set Nail & KC Remon. tag SE side 6" Elm	N75°E	88.34'
NW cor. hse. fnd.	S45°E	181.50'
Kent Co. Mon. at N 1/4, Sec. 2, T8N, R12W	S90°E	46.46'

Monument is in C/L 10 Mile Rd. blacktop



Signed by Kirk Breitels

Date 3/20/95

Surveyor's Michigan License No. 30077