

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
99 MAY 21 AM 8:33
REG. OF DEEDS
Luigi Spand

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N	R 12W	K-5
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

10632

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breitels, in a field survey on April 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5	1837	GLO	Whitcomb	Set Post
	1981	LCRC #2318	Nederveld	3/4" Round Iron
	1982	LCRC #2894	Jonker	Set Kent County Monument
	1995	LCRC #8316	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/30/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 6-3-82 and was recorded per LCRC#2894.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Round Iron he found. Said Iron checks with LCRC #2318.

LCRC #2894	Nail & Remon. tag 8" Poplar	S70°W	8.60'	LCRC #8316	Nail & Remon. tag 10" Poplar	S70°W	8.43'
	Nail & Remon. tag 10" Poplar	S00°W	22.96'		Nail & Remon. tag 14" Poplar	S00°W	23.05'
	Nail & Remon. tag Tw. 8" Mpale	S60°E	23.92'		Nail & Remon. tag Tw. 10" Maple	S60°E	32.93'
	Nail & Remon. tag 4" Elm	N55°E	25.55'		Nail & Remon. tag 4" Elm	N55°E	25.60'
	Nail & Remon. tag 6" Maple clump	N00°E	16.76'		Nail & Remon. tag 6" Maple clump	N00°E	16.68'
	On N-S fence				On N-S fence & in swampy area		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5	Standard Kent County Monument		
	Nail & KC Remon. tag N. side 10" Poplar	S70°W	8.43'
	Nail & KC Remon. tag W. side 14" Poplar	S00°W	23.05'
	Nail & KC Remon. tag N. side Tw. 10" Maple	S60°E	32.93'
	Nail & KC Remon. tag NW side 6" Elm	N55°E	25.60'
	Nail & KC Remon. tag E. side 6" Maple clump	N00°E	16.68'
	On N-S fence & in swampy area		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 4/30/98