

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>9N</u> R <u>12W</u> | <u>K-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:30
REG. OF DEEDS
Lucy Bond

10488

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--------------------------|-----------|--|
| K-8 1837 GLO | Whitcomb | Set Post |
| 1926-54 Williams & Works | | Fence Cor. - Iron |
| Kent Co. Wits | | Iron |
| 1985 LCRC #4310 | Kolehouse | Set Kent County Monument |
| 1995 LCRC #8319 | Breitels | Set Kent County Monument over Kent County Monument |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98

CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 8-31-85 and was recorded per LCRC#4310.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found. Said Iron checks with Kent Co. Wits. and Williams & Works information.

LCRC #4310	Nail & Remon. tag 6" Maple North 19.20'	LCRC #8319	Nail & Remon. tag 10" Maple N00°E 19.03'
	Nail & Remon. tag 10" Ash N35°E 8.62'		Nail & Remon. tag 12" Ash N35°E 8.64'
	Nail & Remon. tag 24" Maple East 29.03'		Nail & Remon. tag 28" Maple S90°E 28.99'
	Nail & Remon. tag 14" Maple N55°W 24.73'		Nail & Remon. tag 18" Maple N55°W 24.67'
	On fence lines running N-E-W		N. shore of "Lake Emily" is South 35' ±
	N. shore "Lake Emily" is South 50' ±		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-8 Standard Kent County Monument
- | | |
|---|--------------|
| Nail & KC Remon. tag E. side 10" Maple | N00°E 19.03' |
| Nail & KC Remon. tag SE side 12" Ash | N35°E 8.64' |
| Nail & KC Remon. tag N. side 28" Maple | S90°E 28.99' |
| Nail & KC Remon. tag S. side 18" Maple | N55°W 24.67' |
| N. shore of "Lake Emily" is South 35' ± | |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98