

MAR 08 1999 KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located in:	Corner Code #
T 9N R 12W	K-9
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:30
REG. OF DEEDS
W. J. Grand

10489
Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9	1837	GLO	Whitcomb	Set Post
	1972	Kent Co. Wits		Mon. Box
	1977	LCRC #986	Nederveld	1/2" Iron in Mon. Box
	1982	LCRC #2631	Nederveld	Set Kent County Monument in Mon. Box
	1995	LCRC #8320	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 2-19-82 and was recorded per LCRC#2631.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the 1/2" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #986.

LCRC #2631	LCRC #8320
Nail & Remon. tag P. Pole N10°W 34.26'	Nail & Remon. tag P. Pole N10°W 34.28'
Nail & Remon. tag 10" Maple N50°W 101.61'	Nail & Remon. tag 14" Maple N50°W 101.68'
"X" cut on curb S10°E 53.91'	Nail & Remon. tag P. Pole S75°W 104.48'
"X" cut on curb S70°E 40.96'	Nail & Remon. tag Lt. Pole N90°E 58.27'
	"X" cut on curb S10°E 53.88'
	"X" cut on curb S70°E 40.74'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Standard Kent County Monument in Mon. Box			
Nail & KC Remon. tag W. side P. Pole	N10°W	34.28'	
Nail & KC Remon. tag SW side 18" Maple	N50°W	101.34'	
Nail & KC Remon. tag S. side P. Pole	S75°W	104.45'	
Nail & KC Remon. tag N. side Lt. Pole	N90°E	58.23'	
"X" cut on curb	S10°E	53.88'	
"X" cut on curb	S70°E	40.74'	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98