

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

\$7.00  
\$2.00

MAR 08 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

KENT COUNTY  
(County)

Located In: Corner Code #

- |                                    |                            |       |
|------------------------------------|----------------------------|-------|
| 1. Public Land Survey              | T <u>9</u> N R <u>12</u> W | K-10  |
|                                    | T ___ R ___                | _____ |
|                                    | T ___ R ___                | _____ |
|                                    | T ___ R ___                | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___          | _____ |
|                                    | S ___ T ___ R ___          | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___          | _____ |
|                                    | S ___ T ___ R ___          | _____ |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:30  
REG. OF DEEDS  
*Lucy Sand*

10490  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1837 GLO	Whitcomb	Set Post
1972 Kent Co. Wits		Mon. Box
1972 LCRC #295	VanKooten	1/2" Iron in Mon. Box
1982 LCRC #2634	Nederveld	Set Kent County Monument in Mon. Box
1995 LCRC #8321	Breitels	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Kay Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 2-19-82 and was recorded per LCRC#2634.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Gordon d. Nederveld in place of the 3/4" Round Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #295.	
LCRC #2634	LCRC #8321
Nail & Remon. tag P. Pole S40°W 83.42'	Nail & Remon. tag P. Pole S40°W 83.35'
Nail & Remon. tag P. Pole N80°W 85.93'	Nail & Remon. tag P. Pole N80°W 85.93'
NW cor. garage foundation S25°E 162.87'	NW corner garage foundation S25°E 162.87'
Centerline RR crossing sign N10°E 169.05'	Centerline RR crossing sign N10°E 169.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag E. side P. Pole	S40°W 83.35'
Nail & KC Remon. tag S. side P. Pole	N80°W 85.93'
NW corner garage foundation	S25°E 162.87'
Centerline RR crossing sign	N10°E 169.05'
On C/L N-S asphalt road	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98