

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>12</u> W	L-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 OCT -7 AM 10:15
REG. OF DEEDS
Lucy Bond

10728

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitel, in a field survey on July 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-3	1837	GLO	Whitcomb	Set Post
	1935	Kent Co. Wits		1" Iron on Stone
	1978	LCRC #1283	Hay	1" Iron
	1979	LCRC #1313	Nederveld	Iron in Mon. Box
	1982	LCRC #2626	Nederveld	Set Kent County Monument in Mon. Box
	1995	LCRC #8324	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 1-25-82 and was recorded per LCRC #2626.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 DID NOT FIND KENT CO. MON. (road const. 1997). Set Kent County Monument (Harrison) at same location as in 1982 per witnesses from above LCRC's, as set by Gordon D. Nederveld in place of the Round Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #1283 & #1313.

LCRC #2626	LCRC #8324
Nail & Remon. tag T. Pole S60°E 54.60'	Nail & Remon. tag T. Pole S60°E 54.68'
Nail & Remon. tag T. Pole S38°W 57.56'	Nail & Remon. tag T. Pole S38°W 57.53'
Nail & Remon. tag 8" Elm S76°W 34.63'	Nail & Remon. tag 24" Elm S76°W 34.57'
NW cor. hse. fnd. S48°E 115.85'	NW cor. hse. fnd. S48°E 115.80'
SE cor. hse. fnd. N52°W 89.38'	SE cor. hse. fnd. N52°W 89.27'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Standard Kent County Monument		
Nail & KC Remon. tag NE side T. Pole	S60°E	54.64'
Nail & KC Remon. tag SE side T. Pole	S38°W	57.53'
Nail & KC Remon. tag N. side 27" Elm	S76°W	34.57'
NW corner house foundation	S48°E	115.80'
SE corner house foundation	N52°W	89.27'
Nail & KC Remon. tag W. side P. Pole	N20°E	136.49'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 9/24/98