

MAR 08 1999

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey	T9N	R12W	L-5
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

REG. OF DEEDS

98 MAY 21 AM 8:33

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10635

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on April 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-5	1837	GLO	Whitcomb	Set Post
	1961	Kent Co. Wits		1 1/2" Iron
	1971	LCRC #85	Chambers	3/4" Iron in Mon. Box
	1982	LCRC #2897	Jonker	Set Kent County Monument
	1995	LCRC #8325	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/30/98
CHAIRMAN Harry Kube

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 6-1-82 and was recorded per LCRC #2897.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #85.

LCRC #2897	Nail & Remon. tag T. Pole	N40°W	69.0'	LCRC #835	Nail & Remon. tag T. Pole	N40°W	69.11'
	Nail & Remon. tag 18" Walnut	N80°W	60.47'		Nail & Remon. tag 24" Walnut	N80°W	60.58'
	Chiseled "X" on N. end culvert	N70°E	73.52'		Chiseled "X" on N. end culvert	N70°E	73.48'
	Chiseled "X" on curb joint	S45°E	46.80'		Chiseled "X" on curb joint	S45°E	46.80'
	Chiseled "X" on S. end culvert	S70°W	40.60'		On C/L to N-S & E.		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5	Standard Kent County Monument		
	Nail & KC Remon. tag NE side T. Pole	N40°W	69.07'
	Nail & KC Remon. tag S. side 24" Walnut	N80°W	60.47'
	Chiseled "X" on N. end culvert	N70°E	73.52'
	Chiseled "X" on curb joint	S45°E	46.82'
	On C/L asphalt roads to N-S & E.		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 4/30/98