

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 9N	R 12W	L-7
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
99 MAR -5 AM 8:30
REG. OF DEEDS
Lucy Spauld

10493

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7	1837	GLO	Whitcomb	Set Post
	1971	Kent Co. Wits		Mon. Box
	1979	LCRC #1312	Nederveld	3/4" Iron in Mon.. Box
	1982	LCRC #2633	Nederveld	Set Kent County Monument in Mon. Box
	1995	LCRC #8326	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Hubert*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 2-19-82 and was recorded per LCRC#2633.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7	Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the 3/4" Round Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #1312.		
LCRC #2633	LCRC #8326		
Nail & Remon. tag P. Pole	S00°E 53.18'	Nail & Remon. tag P. Pole	S00°E 53.41'
Nail & Remon. tag Guy Pole	N25°W 96.03'	Nail & Remon. tag Guy Pole	N25°W 96.08'
Nail & Remon. tag Guy Pole	N52°E 74.71'	Nail & Remon. tag Guy Pole	N50°E 74.59'
"X" cut on W. end conc. curb	N60°W 67.78'	PK Nail & Remon. tag in curb joint	N60°W 63.49'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7	Standard Kent County Monument
Nail & KC Remon. tag E. side P. Pole	S00°E 53.41'
Nail & KC Remon. tag E. side Guy Pole	N25°W 96.11'
Nail & KC Remon. tag SE side Guy Pole	N50°E 74.59'
PK Nail & KC Remon. tag in curb joint	N65°W 63.49'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98