

**SURVEY & REMONUMENTATION**  
 \$7.00  
 \$2.00  
 MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<b>KENT COUNTY</b> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>12</u> W	<u>L-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 DEC 23 AM 8:59  
 REG. OF DEEDS  
*Lucy St. Paul*

**11081**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Oct. 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-8 1837 GLO Not Set  
 1941-72 Williams & Works Held intersection of fences to N-S & E-W  
 Kent Co. Wits No information

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 10/22/98  
 CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-8 Location of this corner falls inside a sealed Kent County Landfill where entry is restricted by order of Kent County DPW and the Dept. of Natural Resources. Intersection of fences per Williams & Works no longer exist.

The NW 1/4 of this section has had extensive survey work, including a plat along the West 1/8 of this section. Tied together Irons found in the plat and other surveys and computed location of Center - location is 7.4' W. and 1.3' S. of Intersection of 1/4 lines. Since there is little occupation or property splits anywhere else in this section, I recommend the Center (L-8) as computed.

The location described above is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-8 NO CORNER SET AT THIS LOCATION - falls inside sealed and locked landfill.

See LCRC # \_\_\_\_\_ & LCRC # \_\_\_\_\_ for location of witness monuments



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 12/15/98