

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 JUL 14 AM 9:54

Lucy Bond
REG. OF DEEDS

\$7.00
\$2.00

MAR 08 1999

SECTION _____

For corners in KENT COUNTY (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>9</u> N R <u>12</u> W	L-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10658
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on May 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|-----------------|---------------|--------------------------|
| L-9 1837 GLO | Whitcomb | Set Post |
| | Kent Co. Wits | Leaded Stone |
| 1990 LCRC #5603 | Bueche | Set Kent County Monument |
| 1995 LCRC #8327 | Breitels | Kent County Monument |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/25/98
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6-1-90 and was recorded per LCRC #5603.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-9 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" Iron he found. Iron is at side of fence post. Trace of fence N-S & E-W. Kent Co. Wits. all gone.
LCRC #5603
- | | | | | | |
|----------------------------|-------|--------|--------------------------------|-------|--------|
| Nail & Remon. tag 14" Oak | S30°W | 20.50' | Nail & Remon. tag 14" Oak | S30°W | 20.52' |
| Nail & Remon. tag 24" Ash | N60°W | 22.61' | Nail & Remon. tag 24" Ash | N60°W | 22.64' |
| Nail & Remon. tag 6" Maple | N00°E | 22.86' | Nail & Remon. tag 6" Maple | N00°E | 22.93' |
| Nail & Remon. tag 24" Ash | N90°E | 48.24' | Nail & Remon. tag 24" Ash | N90°E | 48.22' |
| Nail & Remon. tag 18" Ash | S20°E | 40.67' | Nail & Remon. tag 18" dead Ash | S20°E | 40.67' |
- On N. side of fence post in swamp

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-9 Standard Kent County Monument
- | | | |
|---|-------|--------|
| Nail & KC Remon. tag E. side 14" Oak | S30°W | 20.52' |
| Nail & KC Remon. tag NE side 24" Ash | N60°W | 22.64' |
| Nail & KC Remon. tag W. side 6" Maple | N00°E | 22.93' |
| Nail & KC Remon. tag S. side 24" Ash | N90°E | 48.22' |
| Nail & KC Remon. tag SW side 18" dead Ash | S20°E | 40.67' |
- C/L 2 track dr. E-W is South 200' ±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 6/25/98