

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>12W</u> | <u>L-10</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-10 1837 GLO	Not Set
1946-60 Williams & Works	Leaded Stone
12" Maple SE 17.90'	12" Maple E 37.23'
12" Maple NW 30.90'	12" Maple SW 33.95'
Kent Co. Wits	Leaded Stone
same witnesses as Williams & Works	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-10 Did not find Leaded Stone - location is in swamp. Two property owners where this corner is a corner of their property told me they have never seen the "Stone." Tied together various surveys (Irons found) in the SW 1/4 by Williams & Works done 1946-60 and found measurements to fit rather well. It appears that other surveyors working in the SW 1/4 have used the same information. Since the location of this corner falls in a swamp and is unstable and hard to get to, I recommend setting witnesses monuments at the 1/8 corners - per Williams & Works information and Irons found - on the North line and East line of the SW 1/4.

The location described above is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-10 NO MONUMENT SET AT THIS CORNER.

See LCRC # 11082 and LCRC # 11083 for location of witness monuments

REG. OF DEEDS
Luis J. Grand

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 23 AM 8:59

11084

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/22/98
CHAIRMAN *Harry Huber*



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 12/15/98