

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

MAR 08 1999

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECORDED FOR RECORD  
98 MAR -5 AM 8:31  
REG. OF DEEDS  
*Jan. 5 1998*

**SECTION**

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                    |  |                |
|------------------------------------|--|----------------|
| 1. Public Land Survey              | T <u>9</u> N R <u>12</u> W             | M-5            |
|                                    | T <u>   </u> R <u>   </u>              | common with    |
|                                    | <del>T <u>9</u>N R <u>12</u>W</del>    | <del>A-S</del> |
|                                    | T <u>   </u> R <u>   </u>              | _____          |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | _____          |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | _____          |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | _____          |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | _____          |

10499

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-5 1837 GLO	Brookfield	Set Post
1961 Kent Co. Wits		1" Iron on Stone
1983 LCRC #3355	Glaza	No. desc. of corner - witnesses given
1983 LCRC #3618	Bueche	Set Kent County Monument in Mon. Box
1995 LCRC #8332	Breitels	Reset Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN Janey Fisher

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-28-83 and was recorded per LCRC#3618.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels at the same location as set in 1983 by John C. Bueche in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC #3355

LCRC #3618	Nail & Remon. tag 54" Sycamore	S10°E 96.38'	Nail & Remon. tag P. Pole	S55°E 99.46'
	Nail & Remon. tag P. Pole	S55°E 99.54'	"X" cut in conc. curb	N60°W 46.22'
	"X" cut in conc. curb	N60°W 46.29'	"X" cut in conc. curb	N20°W 52.81'
	"X" cut in conc. curb	N20°W 52.78'	Nail in Tel. Pole	S30°W 66.27'
	Nail & Remon. tag Tel. Pole	S30°W 66.30'	PK in curb joint	N35°E 32.93'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument		
Nail & KC Remon. tag N. side P. Pole	S55°E 99.50'	
"X" cut in conc. curb	N60°W 46.22'	
"X" cut in conc. curb	N20°W 52.81'	
Nail & tag SE side Tele. Pole	S30°W 66.27'	
PK Nail in curb joint	N35°E 32.93'	
C/L blacktop road West is South 2' ±		
C/L blacktop road East is South 8' ±		
On C/L blacktop road N-S ±		



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98