

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 12W T R T 9N R 11W T R	M-6 common with A-6
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:31
REG. OF DEEDS
Lucy Storch

10500

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 1837 GLO	Brookfield	Set Post
1937 Kent Co. Wits		3/4" Solid Iron
1975 LCRC #818	Spicer	Mon. Box
1977 LCRC #1100	Glaza	3/4" Iron in Mon. Box
1982 LCRC #3192	Bonnema	Set Kent County Monument in Mon. Box
1995 LCRC #8333	Breitels	Reset Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Fanny Heber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 12-9-82 and was recorded per LCRC#3192.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels at the same location as set in 1982 by Douglas W. Bonnema in place of the 3/4" Iron and Mon. Box he found. Said Iron in Mon. Box checks with Kent Co. Wits. and LCRC's #818 & #1100.

LCRC #3192	West	31.57'	Nail & Remon. tag P. Pole	S90°W	31.70'
Nail & Remon. tag P. Pole	N10°W	158.82'	Nail & Remon. tag P. Pole	N10°W	158.95'
Nail & Remon. tag P. Pole	S16°E	142.15'	Nail & Remon. tag 15" Poplar	S16°E	141.73'
Nail & Remon. tag 8" Poplar	S80°E	83.87'	Capped Exxel rered @ S. edge rd.	S80°E	83.87'
Capped Exxel rered @ S. edge rd.	N10°E	88.47'	PK Nail & Remon. tag in curb joint	N45°E	36.26'
Capped Exxel rered @ E. edge rd.					

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument	S90°W	31.70'
Nail & KC Remon. tag N. side P. Pole	N10°W	158.95'
Nail & KC Remon. tag E. side P. Pole	S16°E	141.69'
Nail & KC Remon. tag W. side 18" Poplar	S80°E	83.87'
Capped Exxel rered @ S. edge asph. road	N50°E	55.35'
Nail & KC Remon. tag SE side 4" Pine		
On C/L blacktop roads N-S & E.		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98