

\$7.00
\$2.00
SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 MAR -5 AM 8:31
REG. OF DEEDS
Lucy Bond

For corners in SECTION

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 9N R 12W	M-8
	T ___ R ___	common with
	T 9N R 11W	A-8
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

10502

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8	1837	GLO	Brookfield	Set Post
	1935	Kent Co. Wits		Concrete Monument
	1984	LCRC #4023	Rosema	Set Kent County Monument
	1995	LCRC #8335	Breitels	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 11-20-84 and was recorded per LCRC#4023.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema over top of the Concrete Monument he found. Said Concrete Monument checks with Kent Co. Wits.

LCRC #4023	Nail & Remon. tag 12" Maple	S06°E 379.43'	Nail & Remon. tag 14" Cherry	N77°E 50.15'
	Nail & Remon. tag 8" Elm	N05°E 274.80'	Nail & Remon. tag clump 16" Oaks	S90°E 39.22'
	Nail & Remon. tag 10" Cherry	N77°E 50.20'	Nail & Remon. tag clump 12" Maples	N20°E 129.27'
	Nail & Remon. tag clump 12" Oak	S90°E 39.15'	1" Iron - East - 32.67'	
	C/L of N-S b.t. road - West 1'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Standard Kent County Monument				
	Nail & KC Remon. tag NW side 14" Cherry	N77°E	50.15'	
	Nail & KC Remon. tag S. side clump 16" Oaks	S90°E	39.22'	
	Nail & KC Remon. tag W. side clump 12" Maples	N20°E	129.27'	
	Nail & KC Remon. tag NW side 4" Maple	N60°E	38.59'	
	1" Iron - East - 32.67'			
	Centerline of N-S blacktop road is West 1'			



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/19/98