

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

KENT COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey

T 9N R 12W	M-10
T R	common with
T 9N R 11W	A-10
T R	
- 2. Property Controlling in Section

S T R	
S T R	
- 3. Miscellaneous Property in Sec.

S T R	
S T R	

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 MAR -5 AM 8:31
 REG. OF DEEDS
Lucy Stovall

10504
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|-----------------------|------------|--------------------------|
| M-10 1837 GLO | Brookfield | Set Post |
| 1962 Kent Co. Wits | | Concrete Monument |
| 1965 Williams & Works | | Concrete Monument |
| 1984 LCRC #4025 | Rosema | Set Kent County Monument |
| 1995 LCRC #8337 | Breitels | Kent County Monument |

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 2/19/98
 CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 11-20-84 and was recorded per LCRC#4025.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 3/4" Iron he found over a Concrete Monument. Said Iron over Conc. Mon. checks with Kent Co. Wits. and Williams & Works information.

- | | | | | | |
|------------|----------------------------------|---------------|------------|----------------------------------|---------------|
| LCRC #4025 | Nail & Remon. tag 12" Ash | N85°W 46.13' | LCRC #8337 | Nail & Remon. tag 20" Ash | N85°W 46.15' |
| | Nail & Remon. tag 12" Ash | N30°W 64.29' | | Nail & Remon. tag 20" Ash | N30°W 64.28' |
| | Nail & Remon. tag 10" Ash | N50°E 75.70' | | Nail & Remon. tag 18" Ash | N50°E 75.72' |
| | Nail & Remon. tag dbl. 15" Maple | S39°E 103.32' | | Nail & Remon. tag dbl. 20" Maple | S39°E 103.23' |
| | Nail & Remon. tag 15" Ash | S60°W 52.80' | | Nail & Remon. tag 22" Ash | S60°W 52.76' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 Standard Kent County Monument
- | | |
|---|---------------|
| Nail & KC Remon. tag N. side 20" Ash | N85°W 46.15' |
| Nail & KC Remon. tag SW side 20" Ash | N30°W 64.28' |
| Nail & KC Remon. tag SE side 18" Ash | N50°E 75.72' |
| Nail & KC Remon. tag SW side dbl. 20" Maple | S39°E 103.23' |
| Nail & KC Remon. tag SE side 22" Ash | S60°W 52.76' |
- On C/L N-S blacktop road
 C/L blacktop road to East is South 4'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 2/19/98