

SURVEY & REMONUMENTATION

MAR 08 1999

\$7.00  
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located in: Corner Code #

- 1. Public Land Survey
 

T	_____	R	_____
T	_____	R	_____
T	_____	R	_____
T	_____	R	_____
- 2. Property Controlling in Section
 

S 25	T9N	R12W	Wit Mon on
S	T	R	N-S 1/4 line
- 3. Miscellaneous Property in Sec.
 

S	T	R	_____
S	T	R	_____

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 1946-60	GLO Survey	Whitcomb Williams & Works	Not Set Set and used Iron at 1/8 corner on N-S 1/4 line between S 1/4 corner and C 1/4 corner (Stone)
-----------------	---------------	------------------------------	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron Pipe at 1/8 corner that fits Williams & Works measurements  $\pm$ . Said Iron Pipe fits other Irons found in the SW 1/4. It appears all other surveys in the SW 1/4 fit this 1/8 corner and respective measurements  $\pm$ .  
This Iron Pipe per Williams & Works is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the Witness Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Kent County Witness Monument in place of the Iron Pipe			
Nail & KC Remon. tag E. side 33" Oak	S35°E	41.90'	
Nail & KC Remon. tag N. side 24" Pine	S75°E	52.04'	
SW corner brick planter - at grade	N60°E	100.23'	
Iron Pipe	North	33.02'	
Nail & KC Remon. tag W. side 16" Oak	N05°W	65.04'	
Nail & KC Remon. tag SW side 27" Oak	N40°W	39.93'	



Signed by [Signature]

Surveyor's Michigan License No. 30077

Date 12/15/98

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 98 DEC 23 AM 8:59  
 REG. OF DEEDS  
*[Signature]*

other code # 6  
11083

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													