

**SURVEY & REMONUMENTATION**

OCT 28 1994

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

94 SEP 28 AM 9:07

For corners in **COMMISSION**

Kent (County)	Located In:	SPENCER TWP. Corner Code ##
1. Public Land Survey	T <u>10N</u> R <u>9W</u>	D-12
	T _____ R _____	cen. sec. 32
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*  
 REG. OF DEEDS

**7137**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	▲	33	34	35	36							
13													

I, Wallace E. Glaza, in a field survey on August 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

<b>Williams &amp; Works</b>	L.C.R.C. No. 1054 (Clayton Hay)
1894 - Found stake & gas pipe set by "Baker" 2654.5' East of West 1/4 corner and 2648' West of the East 1/4 corner.	Found "T" iron in gravel road, 8.30' South centerline travel.
1968 - Iron set at intersection of 1/4 lines per section survey - not witnesses in notes. Did not find gas pipe. G.L.O. did not set.	18" Maple North 32.00'
	14" Dbl Maple NE 40.90'
	10" Maple WNW 44.20'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-12 (Center of Section 32, T10N, R9W, Spencer Township, Kent County, Michigan)  
 Found "T" iron. Verified location from witnesses and Williams & Works distances and angles. "T" iron is 0.44' South and 2.29' West of intersection of 1/4 line. Accepted "T" iron as center of Section 32. Replace "T" iron with standard 4" x 30" Kent County Monument (Harrison).

West 1/4 corner to center - 2646.97'  
 North 1/4 corner to center - 2664.81'  
 East 1/4 corner to center - 2655.81'  
 South 1/4 corner to center - 2655.09'


P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 8/25/94  
 CHAIRMAN *Harry Huber*

The selected location is accepted by as the best available location of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-12 (4" x 30" Kent County Monument)

1) Remon tag & nail in N side 18" Quad Maple	S85°W	31.77'
2) Remon tag & nail in NW side 12" Maple	S61°W	21.46'
3) Remon tag & nail in SW side 14" Maple	N58°W	43.97'
4) Remon tag & nail in SW side P-pole (6' above ground)	S66°E	124.01'
5) Centerline East-West gravel road	North	8'



Signed by Wallace E. Glaza  
 Glaza & Associates, Inc. 31592  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 8-30-94