

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAY 22 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Spencer Township	Corner Code #
1. Public Land Survey	T 10N	R 9W	D-13
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

REG. OF DEEDS

[Handwritten Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC - 8 AM 10: 01

11530

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on August 12 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	1837	G.L.O. Notes	Cathcart	Set Post
	1938-67	Witness Map	K.C. Surveyor	Monument
	1977	L.C.R.C. #1054	C.S. Hay	Iron in Monument Box
	1981	L.C.R.C. #1518	Williams & Works	Fnd. Conc. Monument / Set K.C. Monument
	1992	L.C.R.C. #6455	John Bueche	K.C. Monument

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2								
3													
4	7	6	5	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	28	25							
11													
12	31	32	33	34	35	36							
13													

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/28/99
CHAIRMAN *[Handwritten Signature]*

Note: This corner is not common with D-1, T9N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 12/12/80 and was recorded per L.C.R.C. #1518.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found a Standard Kent County Monument on the C/L of 16 Mile Road (gravel) running East and West per L.C.R.C.'s #1518 and #6455 as set by Williams & Works in place of a concrete monument they found which checked L.C.R.C. #1054 and the K.C. Surveyor's records.

L.C.R.C. #1518

18" Maple S..S.W. 138.34'

L.C.R.C. #6455

- Nail & K.C. Remon. Tag in S side 8 Poplar N 60° W 65.50' (m. 65.51')
- Nail & K.C. Remon. Tag in W side 6" Elm S 25° W 29.14' (m. 29.15')
- Nail & K.C. Remon. Tag in W side 10" Elm S 75° E 68.77'
- Nail & K.C. Remon. Tag in S side dbl. 6" Oak N 75° E 82.75' (m. 82.73')
- Nail & K.C. Remon. Tag in W side 12" Poplar N 00° E 40.42' (m. 40.38')
- 1' S of C/L gravel road E & W
- K.C. Mon. (N 1/4 5, 9-9) West 138.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Standard Kent County Monument

- Nail & K.C. remon. tag on S side 8" Poplar N 60° W 65.51'
- Nail & K.C. remon. tag on W side 6" Elm S 25° W 29.15'
- Nail & K.C. remon. tag on W side 10" Elm S 75° E 68.77'
- Nail & K.C. remon. tag on W side 12" Poplar North 40.38'
- Nail & K.C. remon. tag on S side dbl. 6" Oak N 75° E 82.73'
- K.C. Mon., D-1, T9N, R9W, West 138.79'

Signed by *[Handwritten Signature]* Date _____

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

