

\$7.00  
\$2.00

**SURVEY &  
REMONUMENTATION**

MAY 22 2000

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in SECTION

Kent (County)	Located in: Spencer Township	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>9W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS  
*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 DEC - 8 AM 10: 02

11534

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on September 29 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1837	G.L.O. Notes	Cathcart	Set Post
	1900-27	Records	Williams & Works	Stake
	1984	L.C.R.C. #4014	John Bueche	Fnd. 1-1/2" Iron / Set K.C. Monument
	1989	L.C.R.C. #5076	John Bueche	K.C. Monument
	1997	L.C.R.C. #9921	Kirk Breitels	K.C. Monument

Note: This corner is not common with H-1, T9N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 10/17/84 and was recorded per L.C.R.C. #4014.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/28/99  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found a Standard Kent County Monument 3' ± West and 10' ± North of the C/L intersection of 16 Mile Road (gravel) running East and Podunk Avenue (gravel) running North and South per L.C.R.C.'s #5076 and #9921 as set by John Bueche in place of a 1-1/2" iron he found which checked with L.C.R.C. #4014.

L.C.R.C. #4014

L.C.R.C. #9921

K.C. Remon. tag & nail in NE side dbl. 24" Willow S 10° E 83.12'  
K.C. Remon. tag & nail in S side 30" Maple S 65° E 88.32'  
K.C. Remon. tag & nail in E side Power Pole N 25° E 139.87'  
C/L N-S gravel road is East 3'+/-  
C/L gravel road East is South 10'+/-


Nail & KC Remon. tag NE side 26" Willow S10°E 83.15'  
Nail & KC Remon. tag S. side 38" Maple S65°E 88.26' (m. 88.32')  
Nail & KC Remon. tag E. side P. Pole N25°E 139.81' (m. 139.78')  
Nail & KC Remon. tag E. side Tri. 12" Maple N25°W 89.95'  
C/L N-S gravel rd. is East 3' +/-  
C/L gravel rd. East is South 10'+/-

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument

- \* Nail & K.C. remon. tag on E side P. pole N 25° E 139.78'
- Nail & K.C. remon. tag on S side 38" Maple S 65° E 88.32'
- Nail & K.C. remon. tag on NE side 26" Willow S 10° E 83.15'
- Nail & K.C. remon. tag on E side triple 12" Maple N 25° W 89.95'
- SW cor. conc. house fndn. N 50° E 101.70'
- C/L of gravel road running N-S, East 3' ±
- C/L of gravel road running E, South 10' ±
- K.C. Mon. H-1, T9N, R9W, West 120.45'



Signed by [Signature] Date 10-29-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854