

W

Kent County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

53 JUL 23 AM 10:30

For corners in

<u>Kent</u> (County)	Located In:	Corner Code #
	10N 9W	J-9(S 1/4, 23)
1. Public Land Survey	T ___ R ___	Spencer Twp.
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

W. J. Bond
REG. OF DEEDS

6794

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John C. Bueche in a field survey on April, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 J-9 LCRC #5299, Dec., 1989, falls in Lake
 Set by single proportional measurement on the S Line of Sec. 23 (2639.17'-2639.17')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Set point as per above (2639.35'-2639.35')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Set wit. cor. 746.87' N of S 1/4 cor. Sec. 23 on the N-S 1/4 Line Sec. 23 (See LCRC 6790)
 Set wit. cor. 1030.76' E of S 1/4 cor. Sec. 23 on the S Line of Sec. 23 (See LCRC 6791)
 Set wit. cor. 737.43' W of S 1/4 cor. Sec. 23 on the S. Line of Sec. 23 (See LCRC 6792)
 Set wit. cor. 956.30' S of S 1/4 cor. Sec. 23 on the N-S 1/4 Line Sec. 26 (See LCRC 6793)
 See Liber 255 page 17 for section survey of Sec. 23
 See Liber 255 page 18 for section survey of Sec. 26

Signed by John C. Bueche Date June 10, 1993
 Surveyor's Michigan License No. 13027

